



# **T-BERD/MTS 8000E Platform**

**Uni-Directional Fiber  
Characterization**

**Test Procedure**

*This document describes the procedure to configure and perform the characterization of an optical fiber link using a mated pair of T-BERD/MTS 8000 test platform and an OBS5x0 broadband source.*



**T-BRERD/MTS 8000 unit**



**OBS 5x0**

# TEST SET REVIEW AND PREPARATION

## FIBER CHARACTERIZATION OVERVIEW

Fiber Characterization is a comprehensive suite of point-to-point physical layer optical tests that measures and determines the quality and potential transmission capability of a given optical fiber.

Fiber Characterization testing, prior to network element installation, provides a true picture of the network's physical characteristics and expected performance for various technologies (10/40/100Gb/s Ethernet, DWDM, CWDM)

It enables the equipment manufacturer to provide the operator with the most cost-optimized solution for a given bit rate.

A uni-directional fiber characterization suite of test includes:


- Connector end face inspection
- Uni-directional OTDR testing
- Chromatic Dispersion (CD) testing
- Polarization Mode Dispersion (PMD) testing
- Attenuation Profile (AP)

## RECOMMENDED TEST EQUIPMENT AND ACCESSORIES

Prior to testing you will need to locate the following test equipment and accessories. Most of this equipment is found in the Fiber Characterization Test Kit you have purchased.

### Test units

- 1xT-BERD 8000 unit equipped with 3 test modules, built-in Power meter, VFL and talkset.
- 1xOBS5x0 Broadband Source for PMD/AP/CD testing



## Accessories

- 2x inspection scopes P5000i - one for each site



***It's recommended to equip the far end user with a stand-alone VIAVI P5000i unit attached to a handheld display***

- 1x connector tip boxes for P5000i with 7 tips. one for each site



- 2 x 3m (10 inch) fiber patchcords 2 for each site



- Fiber optic cleaning tools (not included in the kit)



## FIBER CHARACTERIZATION TEST CRITERIA

Shown below are the pertinent criteria, pass/fail thresholds and associated Standards for testing fiber. The Viavi fiber characterization test kit will measure all these parameters.

Parameter	JDSU	Relevant international standard
Fiber Slope	0.35 dB / km @ 1310nm 0.25 dB / km @ 1550nm	ITU-T G.650.3, IEC-60793-1-22, TIA-455-133-A-2003
Insertion Loss (IL)	Varies by span	ITU-T G.650.1, IEC 60793-1-40, TIA/EIA-455-78B
Optical Return Loss (ORL)	>30dB	IEC 61300-3-6, IEC 61300-3-7, EIA/TIA-455-107A
Splice Loss	<0.3 dB 1-way <0.15 bidir avg	ITU-T G.650, IEC 60874-1, IEC 61073-1, TIA/EIA-455-8
Connector Loss	<0.5 dB 1-way <0.3 bidir avg	ITU-T G.650, IEC 60874-1, IEC 61073-1, TIA/EIA-455-8
Connector Reflectance	<-35dB	ITU-T G.650, IEC 60874-1, IEC 61073-1, TIA/EIA-455-8
PMD	5ps for 10GE 10ps for 10Gb/s 2.5ps for 40G 25ps for 100GE (DP-QPSK)	ITU-T G.650.2, IEC 60793-1-48, TIA-455-113
CD	738 ps/nm for 10GE 1000 ps/nm for 10Gb/s 80ps/nm for 40G 30,000 ps/nm for 100GE (DP-QPSK)	ITU-T G.650.1, IEC 60793-1-42, ANSI/TIA-455-175-B (2003)
AP	0.25 dB:km at 1550 nm 0.25 dB/km at 1600 nm	TIA/EIA-455-61, TIA/EIA-455-78, IEC 61300-3-7, IEC 60793-1-1

## SOFTWARE DOWNLOADS

Verify your test equipment has the latest software update to ensure proper operation. This includes TBERD 6000A, TBERD 8000, FiberChek PRO inspection for P5000i fiber scopes. Software conflicts between P5000i scope and T-BERD/MTS units may impact the test process.

**Make sure the 6000 and 8000 units have the same software version.**

Use the following internet links to check for latest SW and follow upgrade procedure.

### TBERD 8000

<http://8k.updatemyunit.net/>



### FiberChek PRO

<http://fcpro.updatemyunit.net/>



**The FiberCheck™ Pro software is used to upgrade the P5000i inspection probe. It requires installation on a PC and direct connection of the P5000i probe.**

## CIRCUIT/LINK INFORMATION REQUIREMENTS

The following information is required before beginning testing. This information should be readily available from Transport Engineering, Service or Dark Fiber Provider.


- Schematic showing all sites on ring
- Span distance information between all sites on ring
- Fiber #s assigned to be used at each location
- Job information
- Required pass/Fail criteria for splice loss, connector loss and reflectance, total ORL
- Expected transmission speed for the tested link (e.g. 10Gb/s, 40Gb/s, 100Gb/s...)


### **Prior to starting a test sequence:**

- 1 Locate all physical fiber ports on panel
- 2 Identify the fiber under test (FUT) and the fiber used for the datalink connection.


## INSPECT AND CLEAN CONNECTORS

Before connecting a fiber into a test module or fiber panel, inspect and clean the bulkhead and the fiber jumper connectors.

- 1 Connect the P5000i video inspection scope to both units USB port (any)
- 2 Press the **ON/OFF** hard key on the both units to turn-up.
- 3 Press the **HOME** hard key on the T-BERD/MTS 8000
- 4 Press the **SYSTEM** hard key on the T-BERD/MTS 6000A or **HOME** if 6000AV2
- 5 Activate the Microscope  function on both units by touching twice with your finger or stylus.
- 6 Use the P5000i video inspection scope to verify the connector quality.



Patchcord inspection



Bulkhead and test port inspection

- 7 Use appropriate cleaning material (e.g. IBC™ cleaner, cotton swab, dust air sprays, etc...) and re-inspect to confirm.

## ACTIVATING THE TEST FUNCTIONS – T-BERD/MTS 8000

- 1 Press the **ON/OFF** hard key to turn-up.
- 2 Press the **HOME** hard key when unit is on.
- 3 Activate the test functions by touching twice with your finger or stylus

- 4 Activate 6 test functions:
 

 MTAU	 ECOMP	 EXPERT_OTDR	 PMD	 AP	 CD
--	---	---	---	--	--

## REFERENCING THE TEST FUNCTIONS

The following test functions require REFERENCING before performing field tests:


- Chromatic Dispersion (CD) and Attenuation Profile (AP)

*If the references have already been performed, skip this step.*



## CHROMATIC DISPERSION (CD) REFERENCING PROCESS - IN THE OFFICE

### CONNECTING BOTH UNITS


- 1 Inspect and clean connectors of the fiber jumpers, the COM port of the T-BERD/MTS 8000 and the OTDR port of the T-BERD/MTS 6000A using the P5000i inspection scope.
- 2 Connect the fiber jumper 1 to the T-BERD/MTS 8000 COM port of the MTAU module and to the mating adapter.
- 3 Connect the fiber jumper 2 to the OBS5x0 and to the mating adapter.



## ACTIVATE THE OBS5X0 SOURCE

- 1 Press the **ⓘ** button to turn on the OBS5x0 handheld.
- 2 Press the **Application** hard key  until the CD LED is on.
- 3 Press the **Output** hard key  to activate the Source.

## PERFORMING CD REFERENCING ON THE T-BERD/MTS 8000

- 1 Press the **SETUP** hard key.
- 2 Touch the **CD** tab. 
- 3 Select **Take Reference**  Yes  No  Yes
- 4 Enter the BBS serial number under **BBS Serial Number**

**BBS serial number is displayed at the back of the OBS5x0**


- 5 Press the **START STOP** key
- 6 Confirm by pressing YES when the message  pops up.

**A message *Valid Reference* is displayed in green. If not, verify proper connector cleanliness and interconnections then restart referencing process**




## ATTENUATION PROFILE (AP) REFERENCING PROCESS - IN THE OFFICE

### CONNECTING BOTH TEST SETS (IF NOT ALREADY DONE)


- 1 Inspect and clean connectors of the fiber jumpers, the COM port of the T-BERD/MTS 8000 using the P5000i inspection scope.
- 2 Connect the fiber jumper 1 to the T-BERD/MTS 8000 COM port of the MTAU module and to the mating adapter.
- 3 Connect the fiber jumper 2 to the OBS5x0 and to the mating adapter.




## ACTIVATE THE OBS5X0 SOURCE

- 1 Press the  button to turn on the OBS5x0 handheld.
- 2 Press the **Application** hard key  until the CD LED is on.
- 3 Press the **Output** hard key  to activate the Source.

## PERFORMING AP REFERENCING ON THE T-BERD/MTS 8000

- 1 Press the **SETUP** hard key.
- 2 Touch the  AP tab.
- 3 Select **Take Reference** Yes  No  Yes .
- 4 Enter the BBS serial number under **BBS Serial Number** 14  14 .



*BBS serial number is displayed on the T-BERD / MTS6000A Results page*

- 5 Press the **START STOP** key
- 6 Confirm by pressing YES when the message  **Take New Reference Confirm ?** pops up.

*A message **Valid Reference** is displayed in green. If not, verify proper connector cleanliness and interconnections then restart referencing process*

## HIGH LEVEL DIRECTORY CREATION - IN THE OFFICE

### CREATING THE HIGH LEVEL STORAGE DIRECTORY - T-BERD/MTS 8000

- 1 Press the **FILE** hard key.
- 2 Highlight desired main disk drive (prefer **Harddisk** drive) by touching with your finger or stylus. Press the soft key  to create a master directory.  
A virtual keyboard will appear to allow you to input a new folder name. Alternatively, you can connect a USB keyboard to input the name.
- 3 Once the folder name is input, press  to validate and create.
- 4 Press **HOME** or **SYSTEM** keys to go back to Home page.

*For each test, the unit will create a sub-directory containing all test results. All sub-directories will be saved into this master directory, unless a new one is created or the selection of the high level directory changes.*




# AUTOMATED LINK CHARACTERIZATION – TEST PROCESS IN THE FIELD

The following procedure describes the AUTOMATED METHOD to configure and perform Fiber Characterization using a mated pair of a T-BERD 8000 and an OBS5x0. Please read the entire procedure BEFORE starting.

## CONNECTING THE FIBER UNDER TEST

- 1 Inspect and clean connectors of the fiber jumpers, the fiber panel port of FUT-1, the COM port of the T-BERD/MTS 8000 and the OBS port using the P5000i inspection scope.
- 2 Connect the fiber jumper to the fiber panel port of the fiber under test FUT-1 and to the test set: one connected to the T-BERD/MTS 8000 COM port of the MTAU module and one connected the OBS5x0 source.



## SETTING OTDR PASS/FAIL CRITERIA ON THE 8000 UNIT

*You don't need to go through this step if the pass/fail criteria had previously been set up.*

- 1 Press the **SETUP** Hard key on both units
- 5 Go to the SM-OTDR tab
- 6 Press the soft key **Alarms**
- 7 Select Alarm level to "Fail" 

Alarm Level	Fail	None	Fail	Warning
-------------	------	------	------	---------
- 8 Set the thresholds to 

Threshold	JDSU Default	JDSU Default
-----------	--------------	--------------

 or define your own criteria.

## LAUNCHING THE LINK CHARACTERIZATION SCRIPT

- 1 Press the **SCRIPT** hard key on the 8000 unit.
- 2 Select the function 

2 Scripts
1: Link_Characterization

 by touching with your finger or stylus.
- 3 Press the soft key **Launch** to enter the script configuration menu.

*If both test sets have the latest version loaded, touch the from the home page to be directed to the script main page immediately*

## CONFIGURING THE TEST SEQUENCE

- 1 Checkmark the desired test functions to include in the characterization sequence
- 2 Make sure "Full auto test" is checked.

**Test Setup :**

Connector Inspection

OTDR Unidir.

OTDR Bidir.     Auto

OEO                     Manual

Bi-directional IL/ORL

CD

PMD

AP

BBS

Full auto test (DATALINK)

## CONFIGURING THE JOB TYPE AND LINK DESCRIPTION ON BOTH UNITS

- 1 Check "Fiber Span testing" as Job Type
- 2 Enter Link information.

**Job Type :**

Cable commissioning     Fiber Span testing

**Link Description :**

Enter Cable/Link Id    Select bit/rate in drop down list    Enter fiber number

Enter Fiber identification

Enter both end locations

Add job/work# info. and comments if required

Different extremities

Local Cable Id    CABLE

Local Fiber Id    X23

A Location    LA

B Location    LB

Rate    10GEth

Job/Ticket #    TH78

Comment    FC TEST #2

Local Fiber #    3

Direction    A->B

*All test files will be saved into the directory automatically created as per [Local Fiber Id] [Local Fiber #].*

## CONFIGURING THE "RESULTS" SUMMARY TABLE

This summary table, located at the bottom of the script main page, enables to review selected values at the end of the script test sequence. A Pass/Fail status is associated to the table.



<b>Summary Results :</b>								
Fiber #	Distance	Avg. IL 15	ORL oe 15	PMD	AP 1550	CD 1550	CDC 1550	status

*You don't need to go through this step if the table has previously been configured.*

- 1 Press the Select Results To Display to access the selection list.
- 2 Highlight one parameter in the column **Available results** .
- 3 Press the soft key Add Result in order to select the parameter and see it in the column **Results to display** .
- 4 Repeat steps 1 to 3 until you have selected all the parameters. Maximum 7.




- 5 Press the soft key **Validate** in order to acknowledge the selection.

## ACTIVATE THE OBS5X0 SOURCE


- 1 Press the **1** button to turn on the OBS5x0 handheld.
- 2 Press the **Application** hard key  until the PMD LED is on.
- 3 Press the **Output** hard key  to activate the Source.

## STARTING A TEST SEQUENCE


### On the T-BERD/MTS 8000

- 1 Press the **Start** soft key or the  button on both units
- 2 When message  **Start SM-OTDR measurement?** appears, press **Yes** to start OTDR test
- 3 Notify far end user when the following prompt appears  **Check source. Start PMD measurement?** but **DO NOT** press **Yes** until far end user confirmed PMD source function is activated.


### On the OBS 5x0 side

- 4 When notified by the 8000 user, press the **Output** hard key  to activate the Source
- 5 Notify the far end user

### On the T-BERD/MTS 8000

- 6 Press **Yes** to start PMD measurement.
- 7 Notify the far end user when the following prompt appears  **Check source. Start AP measurement?** but **DO NOT** press **Yes** until far end user confirmed AP source function is activated.


### On the OBS 5x0 side

- 8 When notified by the 8000 user, press the **Application** hard key  until the AP LED is on
- 9 Notify the far end user

### On the T-BERD/MTS 8000

- 10 Press **Yes** to start AP measurement
- 11 Notify far user when the following prompt  **Check source. Start CD measurement?** appears but **DO NOT** press **Yes** until far end user confirmed CD source function is activated.

### On the T-BERD/MTS 6000A OBS5x0

- 12 When notified by the 8000 user, press the **Application** hard key  until the AP LED is on
- 13 Notify the far end user

### On the T-BERD/MTS 8000

- 14 Press **Yes** to start CD measurement

- 15 Notify the far end user when measurement completed

**On the OBS5x0 side**

- 16 When notified by the 8000 user, Press the Output hard key Source



to de-activate the

- 17 Notify the far end user.

### TEST NEXT FIBER



Once test completes, a message will appear :

- 1 Verify results in RESULTS SUMMARY table
- 2 If results are satisfactory Swap FUT-1 and FUT-2 at fiber panel (at each site) and press  on TB8000. Fiber number will automatically increment and a new results folder will be created

***Before testing next fiber, make sure the fiber description (fiber number, location...) has been correctly setup in the Link Characterization Script setup page.***

- 3 Notify the far end user to do the same
- 4 If results are un-satisfactory, perform steps to remedy problem(s) and press
- 5 Notify the far end user to do the same
- 6 If no further testing is required at site, press  and EXIT script.
- 7 Move To Next Site For Testing





**Viavi Solutions**

<b>North America:</b>	<b>1.844.GO VIAMI / 1.844.468.4284</b>
<b>Latin America</b>	<b>+52 55 5543 6644</b>
<b>EMEA</b>	<b>+49 7121 862273</b>
<b>APAC</b>	<b>+1 512 201 6534</b>
<b>All Other Regions:</b>	<b><a href="https://viavisolutions.com/contacts">viavisolutions.com/contacts</a></b>
<b>email</b>	<b><a href="mailto:TAC@viavisolutions.com">TAC@viavisolutions.com</a></b>